


DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate
Item No.

Name of Work : Construction of Culvert and Improvement of Drain and Cement Concrete road in Kothihosalli Maruthinagara in ward no8 (kodigehalli) Kodigehalli Sub Division.

Sl. No	Approved Quantity	Description	Unit	Rates	
				In Figures	In Words
1	218.88	KSRRB 300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH chapter 3. No. 125/ Item No. 19.1/ PWD SR 2013-14	cum	65.88	
2	26.73	KSRB 2-2.1 : earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications, specification, No, KBS 2.1(a) / 2.3.5, No. 5/ Item No. 2.3/ PWD SR 2013-14	cum	151.74	
3	143.00	KSRB 100-1 Loading and unloading of stone aggregates / sand/ kanker/ Moorum /soil KSRRB M100-1 Placing tipper at loading with front end loader dumping turning for return trip excluding time for hauled and return trip complete as per specification item No 17.1 page 141 and KSRB	cum	78.24	
4	128.15	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M7.5 with OPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No.	Cum	4290.84	
5	45.95	KSRB 4.2.2 : Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum with superplasticiser @ 3lts conforming to IS9103-	Cum	5639.76	




6	29.87	KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 Page No. 19/ Item No. 4.46/ PWD SR 2013-14	Quintal	7380.72	
7	388.45	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, attached lasters,bittresses,buttresses plinth and string course including cost of all materials, labour complete as per specifications. Specification NO KBS 4.6.2 Page No. 17/ Item No. 4.31/ PWD SR 2013-14	sqm	271.08	
8	270.00	RCC Precast covering slab for drain (10cm thick)	sqm	1245.00	
9	74.00	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC)for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Page No. 19/ Item No. 4.48/ PWD SR 2013-14	Cum	6464.88	

Signature of the Contractor

Reg. No.

Postal Address




Executive Engineer

Byatarayanapura Division

BBMP, Bangalore - 92

ಕರಡು ಬೆಂಡರ್ ಪೆಡ್ಕೊಲನ್ನು ತಿದ್ದು ಪಡಿ ಮಾಡಿದಂತೆ/
ತಿದ್ದುಪಡಿ ಇಲ್ಲದೆ ಅನುಮೋದನೆ ನೀಡಲಾಗಿದೆ.
ತಿದ್ದುಪಡಿಗೆ ಸಂಖ್ಯೆ.....Nil.....


21/10/2013

Superintending Engineer
Yelahanka Zone
BBMP, Bangalore-92